




नेपाल सरकार  
स्वास्थ्य तथा जनसंख्या मन्त्रालय  
भरतपुर अस्पताल, चितवन  
वोलपत्र सम्बन्धि सूचना

(प्रथम पटक प्रकाशित मिति २०७९।०५।०७)

यस अस्पतालको कुरुवा घरमा क्यान्टिन संचालन गर्न आवश्यक पूर्वाधार निर्माणकार्यहरु वोलपत्रको माध्यम बाट गर्नुपर्ने भएकोले मु.अ.क.मा दर्ता भएका इच्छुक ईजाजत प्राप्त सप्लायर्स, विक्रेता तथा निर्माण व्यवसायीहरुले रितपूर्वकको वोलपत्र तपशिलको शर्तहरु पालना हुने गरी भरतपुर अस्पतालको [Website- eProcurement System \(bharatpurhospital.gov.np\)](http://Website-eProcurement System (bharatpurhospital.gov.np)) मार्फत पेश गर्नु हुन यो सूचना प्रकाशित गरिएको छ ।

**शर्तहरु:**

१. आ.व. २०७९/०८० का लागि नविकरण भएको इजाजतपत्र, मु.अ.कर दर्ता सहितको स्थायी लेखा नं. प्रमाण पत्र, आ.व.०७७०७८ को करचुक्ताको प्रमाणपत्र तथा अन्य सो कार्यको लागि आवश्यक कागजपत्र पेश गर्नु पर्ने छ ।
२. वोलपत्र खरिद तथा पेश गर्नको लागि तपशिल अनुसारको दस्तुर रकम, उल्लेखित मिति र समयमा यस अस्पतालको रा.वा.बैंक भरतपुरमा रहेको चल्ती खाता नं.१३१०१०००००९६७००१ मा जम्मा गरेको बैंक भौचर पेश गर्नु पर्ने छ ।
३. वोलपत्रपत्र पेश गर्दा जमानत वापत तपशिलमा उल्लेखित रकम रा.वा. बैंक भरतपुर शाखामा कार्यालयको नाम- को.ले.नि.का.चितवन, खाता नं.- ख ३ धरौटी १३१००१०२०३००००, जम्मा गर्न पठाउने कार्यालयको नाम-भरतपुर अस्पताल, चितवन, जम्मा गर्न पठाउने कार्यालयको कोड नं.- ३७०००३१०२ सहितको विवरण भरी रकम जम्मा गरेको सककल बैंक भौचर वा कम्तिमा १२० दिन म्याद भएको यस अस्पतालको नाममा जारी भएको विड वण्ड पेश गर्नुपर्नेछ ।
४. वोलपत्र तपशिलमा उल्लेखित मिति र समयमा भरतपुर अस्पतालको [Website- eProcurement System \(bharatpurhospital.gov.np\)](http://Website-eProcurement System (bharatpurhospital.gov.np)) मार्फत अनिवार्य रूपमा पेश गर्नु पर्ने छ ।
५. **Upload** भएका वोलपत्रहरु तपशिलमा उल्लेखित मिति र समयमा यस अस्पतालमा वोलपत्रदाता वा निजको प्रतिनिधिको रोहवरमा खोलिने छ । प्रतिनिधि उपस्थित नभए पनि दरभाउपत्र खोल्न बाधा पर्ने छैन । वोलपत्र खरीद गर्ने वा दाखिला गर्ने अन्तिम दिन विदा पर्न गएमा सोको भोलिपल्ट क्रमश उक्त कार्य हुनेछ ।
६. वोलपत्रदाताले कबोल गरेको प्रत्येक आइटमको दररेटलाई (मु.अ.कर बाहेक) अंक र अक्षरमा स्पष्टसँग उल्लेख गर्नुपर्नेछ । अंक र अक्षरमा उल्लेखित दररेटमा भिन्नता भएमा अक्षरलाई मान्यता दिइने छ ।
७. वोलपत्रदाताले कबोल गरेको वोलपत्रमा तोकिएको परिमाण मापदण्ड अनुसार र समयमा कार्य सम्पन्ननसकेमा अन्य उपाय अवलम्बन गरी उक्त कार्य गरिनेछ । त्यसरी कार्यगर्दा वोलपत्रमा उल्लेख गरिएको मुल्यभन्दा बढी पर्न गएमा वोलपत्रदाताको धरौटी रकम वा भुक्तानी गर्न बाँकि रकमबाट असुलउपर गरिनेछ ।
८. निर्माण तथा मर्मतजन्य कार्यको लागि चाहिने सम्पूर्ण सामानहरु स्पेसिफिकेशन बमोजिमको उच्च गुणस्तरको हुनपर्नेछ ।


  
नि. प्र. मे. सु.



९. कुनै बोलपत्र स्वीकृत गर्ने वा नगर्ने वा आशिकं रूपमा स्वीकृत गर्ने सम्पूर्ण अधिकार यस अस्पतालमा सुरक्षित रहनेछ ।
१०. निर्माण तथा मर्मतको लागि प्रयोग भएका सामानहरू निरिक्षण एवं परिक्षण गर्दा सम्मौतामा उल्लेखित गुणस्तर बमोजिमका नभए सम्मौता रद्द गरिनेछ।
११. सम्मौता गरी कार्य नगर्ने फर्मलाई नियमानुसार कालोसूचीमा दर्ताको लागि सम्बन्धित निकायमा लेखि पठाइनेछ ।
१२. शर्त रहेको, रीत नपुगेको तथा म्याद नाघी आएको बोलपत्र उपर कुनै कारवाही हुनेछैन । एक फर्म वा सस्थाको नाममा खरिद गरिएको बोलपत्र अर्को फर्मको नामबाट पेश गर्न पाइने छैन ।
१३. बोलपत्रदाताले खरिद कारवाहिमा भाग लिन प्रचलित कानुनअनुसार अयोग्य नभएको, प्रस्तावित खरिद कारवाहिमा आफ्नो स्वार्थ नवाभिएको वाब्यवसाय सम्बन्धि कसुरमाआफुले सजाय नपाएको भनि स्वयं घोषणा पेश गर्नुपर्नेछ । त्यस्तो स्वयम घोषणा सूचना प्रकाशित भएको मिति पछिको हुनु पर्नेछ ।
१४. यसमा नपरेका अन्य कुराहरु सार्वजनिक खरीद ऐन २०६३ र सार्वजनिक खरीद नियमावली २०६४ अनुसार हुनेछ ।
१५. थप जानकारीको लागि यस अस्पतालको इन्जिनियरिङ्ग शाखा/लेखा शाखामा सम्पर्क राख्न सकिनेछ ।

तपशिल

सि. नं.	ठे.नं.	विवरण	जमानत रकम	बोलपत्र दस्तुर	बोलपत्रखरिद गर्ने अन्तिममिति	बोलपत्रदाखिला गर्ने अन्तिममिति	बोलपत्रखोल्ने मिति	कैफियत
१	१४,० ७९।० ८०	कुरुवा घरमा क्यान्टिन संचालन गर्न आवश्यक पुर्वाधार निर्माण	८५,०००।	३०००।	३० औं दिनको वैकड समय भित्र	३१ औं दिनको १२।०० वजे	३१ औं दिनको १।०० वजे	

  
नि. प्र. मे. सु.



Government of Nepal  
Ministry of Health & Population  
**Bharatpur Hospital**  
Chitwan

Job : new canteen shed construction works.  
Location :Kuruwa Ghar, Ground Floor & East side

Tender No :14, 079/080

**BILL OF QUANTITY**

S.N	Description	Quantity	Unit	Per Unit Rate (exclusive of VAT)		Amount	Remarks
				In Figure	In Words		
1	site clearance before and after completion of works.	1	job				
2	Earthwork excavation in medium types soil in foundation including stacking the soil 1 m from the edge of the foundation and 10m hauling distance and 1.5m lift all complete as per instruction by site engineer.	11.04	Cu.mt				
3	filling works: Natural river Gravel filling by laying 15-15 cm layers with water spraying and compacted by labour all complete	109.35	Cu.mt				
4	Stone Soling Work: Supplying and laying stone with sand compaction	16.51	Cu.mt				
5	P.C.C. in 1:3:6 (M10)work for levelling in ground with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all as per instruction and specification all complete.	0.83	Cu.mt				
6	Good quality local chimney made Brickwork in 1:6 C/S mortar Upto Ground Floor in perfect line level finished including material and transportation up to 30m, wetting the bricks,racking the joints and curing the work for at least 7 days all complete.	40.75	Cu.mt				

नि. प्र. मे. सु.



7	(PCC) for RCC works: Preparing Machine Mix concrete grade M20 for foundation, foundation beam, bands etc. with approved quality of cement, sand and crushed stone aggregate (12-40mm) including mixing, compaction, laying, curing etc. in perfect line level and plumb for any size, location and shape all complete work as per drawing, specification and instruction of A/E.	4.81	cu.mt			
8	Steel reinforcement works: Supplying, Cutting, bending & placing of reinforcement bars in position as shown in the drawings and binding by approved binding wires for RCC works with 30 m lead, as per A/E instructions all complete	303.17	kg			
9	Formworks for floorings, slabs, counter slabs, Chhajjas, footings: Supplying, laying, fitting using 19 mm th. plywood formworks with steel adjustable pipe props for floors, sill and lintel bands, slabs etc. and removing after specified time as per instructions etc. all complete	59.15	sq.mt			
10	Plaster Work: Preparing and applying 12.5 mm thick plaster on walls, floors etc, in 1:6 cement sand mortar in proper line and level with curing all complete	330.38	sq.mt			
11	Plaster Work: Preparing and applying 20 mm thick plaster on walls, floors etc, in 1:4 cement sand mortar in proper line and level with curing all complete	82	sq.mt			
12	Preparing, applying, finishing and curing 3mm thick 1:1 cement sand punning on floors, walls, slabs, roofs etc. all complete	117	sq.mt			
13	Dismanteling of Brick wall in cement mortar and removing the	0.51	Cu.mt			

*Prashant*  
नि. प्र. मे. सु.



	debric out of the construction site all complete.						
14	P.C.C. Work: PCC in 1:2:4 (M15) c/s/a, for floors, walls, roofs etc. with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all as per instruction and specification all complete.	9.09	Cu.mt				
15	Supplying, laying, rubbing and finishing of 16 mm thick marble, approved color, on floors, stairs, skirtings etc. on 20 mm thick cement plaster in (1:2) as per instructions all complete	88.25	Sq.mt				
16	Supplying and Laying of Flooring Tiles 600mm X 600mm, 1st class Corridor Floor ceramic VITRIFIED AND HOMOGENOUS tile of approved quality (RAK Dubai or Somany or Nitco or Equivalent) Non-glazed tile on floor surfaces of main building in 1:4 cement sand mortar in perfect line and level , Work all complete as per design, drawings, specification and approval of site Engineer.	31.11	sq.mt				
17	Painting on Interior Wall surface with two coats of plastic emulsion paint of approved color and shade over one coat of primer .	267.5	sq.mt				
18	Painting on exterior Wall surface with two coats of weather coat of approved color and shade over one coat of primer .	161.88	sq.mt				
19	Supplying and fitting metal works with different deections of angles, plates, rods etc. with proper weldings with primer, complete as per instructions and specifications	2318.06	kg				
20	Providing and laying 0.5 mm thick Coloured CGI sheet for roofing all complete	158.54	sq.mt				

*Prashant*  
नि. प्र. मे. सु.



21	Supplying of 0.5mm thk. Colour sheet for ridge and install on site all complete.	17.6	r.mt			
22	Aluminium Doors Works: Supplying and fitting casement Doors, Natural Anodising Aluminium 102 series, 1.1mm th. Fitted 5mm glass and 9mm board at both sides, Full height or Half, both types, with door of same section, fixing with proper nailing, bolting, hinges, rubbers, gaskets etc. as per Drawings, specifications and instructions all complete	8.8	sq.mt			
23	Supplying and fitting 102 series Aluminium sliding window with Ventilator & 90 series flymesh shutter from section (101 x45x1.10)mm and 5mm glass.	10.8	sq.mt			
24	Supplying of materials, fabricating, installing and painting metal channel gate all complete.	20.5	sq.mt			
25	Supplying of materials, fabricating, installing and painting 4.5x20mm metal grill all complete.	4.92	sq.mt			
26	False ceiling works: Supplying materials and Providing, fixing and finishing Gypsum board false ceiling using 12.50 mm thick waterproof gypsum boards of approved brand, fixed to the suspended grid, fabricated and fixed to the soffit of roof / beams and wall using - Gypsteel Ultra ceiling sections - perimeter channels of size 20 mm x 28 mm x 30 mm fixed to the wall using metal screws and nylon sleeves recommended by the site engineer at a spacing not exceeding 600 mm c/c all complete	99	sq.mt			

*Prashant*  
नि. प्र. मे. सु.



27	Chlorinated Poly Vinyl Chloride pipe(hot and cold). or equivalent with CPVC fittings/ specials (Tees, elbows, Unions etc) clamps(m.s plate with nut and bolt with hexagonal screws for clamp in ceiling.wall), nails, including jointing materials,installation of pipes and specials including making holes on walls or floor and repairing the same to its original finish, all complete set as per specification and instruction. (Flow guard or ISI standard or equiv.) .						
	20 mm CPVC (Chlorinated Polyvinyl Chloride) Pipe SDR 11 CTS, 28.1 kg/cm2 (Flowguard or ISI Standard) all complete set with testing and ready for operation.	20	r.mt				
28	Supplying and fixing C P 15 mm ordinary Angle valve with wall flange,cp nipple all complete set all complete set with testing and ready for operation.	1	nos				
29	Supplying and fixing 15 mm CP ordinary Bib Cock all complete set.	2	nos				
30	Stainless Steel kitchen sink, Steel 24"*18"*10" with swan type /single lever mixer all complete set with testing and ready for operation.	1	nos				
31	Supplying and Fixing uPVC pipe 6kg/sqcm all complete set including Fittings as Bend.Tee,Y-branch,vent cowl etc. per specification and instruction. (Panchakanya, marvel, Mangalam, Napatop,Supreme or equi. )						
	75 mm dia PVC Pipe 6 kg/cm2 with Fittings all complete set with testing and ready for operation.	5	r.mt				

*Prashant*  
नि. प्र. मे. सु.



32	Surface Wiring (including materials - PVC channel, switch, ceiling rose, Power socket, Nails, Heavy Metal box etc.) & wages per point	16	points			
33	6 gang one way switch S	3	set			
34	4 gang one way switch S	3	set			
35	4.0mm <sup>2</sup> PVC insulated copper wire from main DB to DB with PVC listic all complete.	50	r.mt			
36	supplying & installing 1 Pole MCB Box all complete.	1	set			
37	Supplying and installing of 6-32 Amp TP MCB ( simens, marlin, gerlin, GE or ISI eqv.) all complete.	1	set			
38	Supplying and installing of 12" Exhaust Fan (Crompton, Almonard, Bajaj or eqv.) all complete.	4	set			
					Sub Total	
					13% VAT	
					Grand Total	
	Name of Company :					
	Address :					
	Date :					
	Signature & Seal of Company :					

*Prashant*  
नि. प्र. मे. सु.