



नेपाल सरकार
स्वास्थ्य तथा जनसंख्या मन्त्रालय
भरतपुर अस्पताल, चितवन
वोलपत्र सम्बन्धि सूचना
(प्रथम पटक प्रकाशित मिति २०७६।१०।१८)

यस अस्पताललाई फोहोर व्यवस्थापनको लागि आवश्यक भएको भवन निर्माण कार्य बोलपत्रको माध्यम बाट गर्नुपर्ने भएकोले मु.अ.क.मा दर्ता भएका इच्छुक ईजाजत प्राप्त सप्लायर्स, तथा निर्माण व्यवसायीहरूले रितपूर्वकको बोलपत्र तपशिलको शर्तहरू पालना हुने गरी यस अस्पतालको Website- www.bharatpurhospital.gov.np को eProcurement System मार्फत पेश गर्नु हुन यो सूचना प्रकाशित गरिएको छ ।

शर्तहरू:

१. आ.व. २०७६/०७७ का लागि नविकरण भएको इजाजतपत्र, मु.अ.कर दर्ता सहितको स्थायी लेखा नं. प्रमाण पत्र, आ.व.०७५।०७६ को करचुक्ता को प्रमाणपत्र तथा अन्य सो कार्यको लागि आवश्यक कागजपत्र पेश गर्नु पर्ने छ ।
२. बोलपत्र खरिद तथा पेश गर्नको लागि तपशिल अनुसारको दस्तुर रकम, उल्लेखित मिति र समयमा यस अस्पतालको रा.बा.बैंक भरतपुरमा रहेको चल्तीखाता नं.१३१००००९६७०१ मा जम्मा गरेको बैंक भौचर पेश गर्नु पर्ने छ ।
३. बोलपत्र पेश गर्दा जमानत वापत तपशिलमा उल्लेखित रकम को.ले.नि.का.चितवनको रा.बा.बैंक, भरतपुर शाखामा रहेको ख ३ धरौटी १३१०२०३०००००० खातामा (जम्मा गर्न पठाउने कार्यालयको नाम-भरतपुर अस्पताल, चितवन, कोड नं.३७०००३१०२ लेखि) रकमजम्मा गरेको सककल बैंक भौचर वा कम्तिमा १२० दिन म्याद भएको यस अस्पतालको नाममा जारी भएको विड वण्ड पेश गर्नुपर्नेछ ।
४. बोलपत्र तपशिलमा उल्लेखित मिति र समयमा यस अस्पतालको Website- www.bharatpurhospital.gov.np को eProcurement System मार्फत अनिवार्य रुपमा पेश गर्नु पर्ने छ
५. Upload भएका बोलपत्रहरू तपशिलमा उल्लेखित मिति र समयमा यस अस्पतालमा बोलपत्रदाता वा निजको प्रतिनिधिको रोहवरमा खोलिने छ । प्रतिनिधि उपस्थित नभएपनि बोलपत्र खोल्न बाधा पर्ने छैन । बोलपत्र खरीदगर्ने वा दाखिला गर्ने अन्तिम दिन विदा पर्न गएमा सोको भोलिपल्ट क्रमश उक्त कार्य हुनेछ ।
६. बोलपत्र दाताले कबोल गरेको प्रत्येक आइटमको दररेटलाई (मु.अ.कर बाहेक) अंक र अक्षरमा स्पष्टसँग उल्लेख गर्नुपर्नेछ । अंक र अक्षरमा उल्लेखित दररेटमा भिन्नता भएमा अक्षरलाई मान्यतादिइने छ ।
७. बोलपत्र दाताले कबोल गरेको बोलपत्रमा तोकिएको परिमाण मापदण्ड अनुसार र समयमा कार्य सम्पन्न नसकेमा अन्य उपाय अवलम्बन गरी उक्त कार्य गरिनेछ । त्यसरी कार्य गर्दा बोलपत्रमा उल्लेख गरिएको मुल्यभन्दा बढी पर्न गएमा बोलपत्र दाताको धरौटी रकम वा भुक्तानी गर्न बाकि रकमबाट असुल उपर गरिनेछ ।
८. भवन निर्माणको लागि चाहिने सम्पूर्ण सामानहरू स्पेसिफिकेशन वमोजिमको उच्च गुणस्तरको हुनपर्नेछ ।
९. स्विकृत बोलपत्रदाताले अस्पतालले उपलब्ध गराएको ठाउँ तथा नक्सा (ड्रइङ डिजाईन) वमोजिमको भवन निर्माण गर्नु पर्नेछ । साथै भवन निर्माण सम्पन्न पश्चात ईन्जिनियर वाट चेक जाँच गरी कार्य सम्पन्न प्रतिवेदन प्राप्त

Medical Superintendent



भएपछि ५ प्रतिशत धरौटि कट्टी , ६।५ प्रतिशत मु.अ.क.कट्टी तथा १।५ प्रतिशत आयकर कट्टी गरी वाकिँ रकम भुक्तानी दिईनेछ ।

१०. कुनै बोलपत्र स्वीकृत गर्ने वा नगर्ने वा आशिक रुपमा स्वीकृत गर्ने सम्पूर्ण अधिकार यस अस्पतालमा सुरक्षित रहनेछ
११. भवन निर्माणमा प्रयोग भएका समानहरु निरिक्षण एव परिक्षण गर्दा समकौतामा उल्लेखित गुणस्तर बमोजिमका नभए समकौता रद्द गरिनेछ ।
१२. संकौता गरी कार्य नगर्ने फर्मलाई नियमानुसार कालोसूचीमा दर्ताको लागि सम्बन्धित निकायमा लेखि पठाइनेछ ।
१३. शर्त रहेको,रीत नपुगेको तथा म्याद नाघी आएको बोलपत्र उपर कुनै कारवाही हुनेछैन । एक फर्म वा सस्थाको नाममा खरिद गरिएको बोलपत्र अर्को फर्मको नामवाट पेश गर्न पाईने छैन ।
१४. बोलपत्रदाताले खरिद कारवाहिमा भाग लिन प्रचलित कानुन अनुसार अयोग्य नभएको, प्रस्तावित खरिद कारवाहिमा आफ्नो स्वार्थ नवाभिएको वा ब्यवसाय सम्बन्धि कसुरमा आफुले सजाय नपाएको भनि स्वयं घोषणा पेश गर्नुपर्नेछ । त्यस्तो स्वयम घोषणा सूचना प्रकाशित भएको मिति पछिको हुनु पर्नेछ ।
१५. यसमा नपरेका अन्य कुराहरु सार्वजनिक खरीद ऐन २०६३ र सार्वजनिक खरीद नियमावली २०६४ अनुसार हुनेछ ।
१६. थप जानकारीको लागि यस अस्पतालको मर्मत शाखा साथै जिन्स शाखामा सम्पर्क राख्न सकिनेछ ।

तपशिल

सि. नं.	ठे.नं.	विवरण	जमानत रकम	दरभाउपत्र दस्तुर	दरभाउपत्र खरिद गर्ने अन्तिम मिति	दरभाउपत्र दाखिला गर्ने अन्तिम मिति	दरभाउपत्र खोल्ने मिति	कैफियत
१	१७, ०७६।०७७	फोहोर व्यवस्थापनको लागि आवश्यक भवन निर्माण कार्य	९००००।-	३०००।-	३० औँ दिनको <u>४१००</u> वजे	३१ औँ दिनको <u>१२१००</u> वजे	३१ औँ दिनको १।०० वजे	


Medical Superintendent



Bharatpur Hospital

Bharatpur, Chitwan

Job: Construction of waste Sorting Facility.(Tender No. 17, 076/077)

Bill of Quantity

S.N	Description	Quantity	Unit	Amount		Remarks
				In Figure	In Words	
1	Site clearance work including cutting of bushes having grith 30cm, cutting & filling at beginning & after completion of work all complete.	1	job			
2	Earthwork in excavation for foundation of post, wall in all kinds of soil with proper line & level, including proper dewatering, necessary backfilling, dressing of sides ramming of bottom if required all complete.	1473.01	cu.ft			
3	Stone soling work in specified thickness in proper line & level with compaction all complete.	1162.91	cu.ft			

Medical Superintendent



4	Plain Cement concrete (PCC) M15 grade for foundation & bands with cement sand & Course aggregates (1:2:4) including mixing, laying, compaction curing finishing etc. all complete.	729.64	cu.ft		
5	3" thick Plain Cement concrete (PCC) M15 grade for flooring with cement sand & Course aggregates (1:2:4) including mixing, laying, compaction curing finishing etc. all complete.	1573.28	sq.ft		
6	Cutting, bending, placing in position as shown in code book & binding by GI wire of reinforcement steel bar for RCC work as per the instruction of Engineer.	896.48	K.G		
7	Stone Masonry work in cement sand mortar (1:4) in Sub structure with approved quality in perfect line and level, finished including packing the joints and curing the works complete.	920.66	cu.ft		
8	Brick Masonry work (Half Brick) in cement sand mortar (1:4) in super structure with approved quality in perfect line and level, finished including packing the joints and curing the works complete.	1116.19	cu.ft		

Medical Superintendent



9	Providing, fabricating and fixing of Post, truss, base plate purline as per specification and instruction of engineer all complete.	3177.09	K.G			
10	Providing & fixing in position 0.5mm C G I colour sheet with necessary hardware fittings all complete	2634.8	sq.ft			
11	Providing & fixing in position 0.45mm Colour C G I Plain sheet Ridge with complete frame with necessary hardware fittings all complete work	53	r.ft			
12	12.5mm thick CM (1:4) plaster works with supply, mixing and curing all work complete.	5675.89	sq.ft			
13	Backfilling work including soil spreading in 15cm layer, each layer being watered and compacted throughly by hand/mechanical rammer as per drawing, specification and instruction.	2022.40	cu.ft			

Medical Superintendent



14	Backfilling of trench from the excavated soil spreading in 15cm layer, each layer being watered and compacted throughly by hand/mechanical rammer as per drawing, specification and instruction.	311.46	cu.ft			
15	Making wooden form work including supply and selection of materials fixing,nailing according to drawings, placing seperators,dismantling forms and hauling upto 30m distance.	1015.90	sq.ft			
16	2 coats of distemper painting of approved manufacture and shade over a coat of primer to surface of any shape, size and height and watering, cleaning and applying required coats of painting to get uniform color & finish complete as per drawing, specification and instructions.	3107.8	sq.ft			
17	2 coats of Exterior weather coat painting of approved manufacture and shade over a coat of primer to surface of any shape, size and height and watering, cleaning and applying required coats of painting to get uniform color & finish complete as per drawing, specification and instructions.	1442.8	sq.ft			

Medical Superintendent



18	supply and installation of porecelene glazed tile in 1:4 cement sand mortar.	652	sq.ft			
19	Supplying & installation of UPVC profile sliding window (frame 80*50mm) white colour with 5mm glass.	160	sq.ft			
20	Supplying and Installation of UPVC profile casement Door (frame 60*60mm) with top glass 5mm and Bottom UPVC panel.	185.5	sq.ft			
21	Supply and installation of PPR pipes (6MPa,32mm OD) and required fitting & fixtures all complete. (50 M pipe)	1	Job			
22	Supply and installation of PVC waste drain pipe (6kgf, 75mm OD) for 2 bucket wash, 2 basin & Autoclave machine all necessary joint & fittings.	1	job			
23	Supply and installation of Local Wash Basin set with all fitting and fixtures and tap for wash.	1	job			

Medical Superintendent



24	Electrification work including 7 no bulb holder, 7 no points for ceiling fan, 5 no power socket and 4 gang, 3 gang, 1 gang one way switch (18 points) with PVC channel surface wiring.	1	job		
Bidder,s Name and Address of company					
Authorized Signature					
Authorized Seal					
Bidding Date					


Medical Superintendent