




नेपाल सरकार
स्वास्थ्य तथा जनसंख्या मन्त्रालय
भरतपुर अस्पताल, चितवन
वोलपत्र सम्बन्धि सूचना
(प्रथमपटक प्रकाशितमिति २०७९।०४।०४)

यस अस्पतालमा गेट निर्माण, ब्लक 'ए' पछाडि मोजाइक टाइल्स लगाउने कार्य बोलपत्रको माध्यमबाट गर्नुपर्ने भएकोले मु.अ.क.मादर्ता भएका इच्छुक ईजाजतप्राप्त सप्लायर्स, विक्रेता तथा निर्माण व्यवसायीहरूले रिटर्नपूर्वकको बोलपत्र तपशिलको शर्तहरू पालना हुने गरी भरतपुर अस्पतालको [Website- eProcurement System \(bharatpurhospital.gov.np\)](http://www.bharatpurhospital.gov.np) मा फर्त पेश गर्नु हुन यो सूचना प्रकाशित गरिएको छ।

शर्तहरू:

१. आ.व. २०७८/०७९ का लागि नविकरण भएको इजाजतपत्र, मु.अ.क. दर्ता सहितको स्थायी लेखा नं. प्रमाण पत्र, आ.व. ०७७/०७८ को करचुक्ताको प्रमाणपत्र तथा अन्य सो कार्यको लागि आवश्यक कागजपत्र पेश गर्नु पर्ने छ।
२. बोलपत्र खरिद तथा पेश गर्नको लागि तपशिल अनुसारको दस्तुर रकम, उल्लेखित मिति र समयमा यस अस्पतालको रा.बा.बैंक भरतपुरमा रहेको चल्लीखाता नं. १३१०१०००००९६७००१ मा जम्मा गरेको बैंक भौचर पेश गर्नु पर्ने छ।
३. बोलपत्र पेश गर्दा जमानत वापत तपशिलमा उल्लेखित रकम रा.बा. बैंक भरतपुर शाखामा कार्यालयको नाम- को.ले.नि.का.चितवन, खाता नं.- ख ३ धरौटी १३१००१०२०३००००, जम्मा गर्न पठाउने कार्यालयको नाम- भरतपुर अस्पताल, चितवन, जम्मा गर्न पठाउने कार्यालयको कोड नं.- ३७०००३१०२ सहितको विवरण भरी रकम जम्मा गरेको सककल बैंक भौचर वा कम्तिमा १२० दिन म्याद भएको यस अस्पतालको नाममा जारी भएको विड वण्ड पेश गर्नुपर्नेछ।
४. बोलपत्र तपशिलमा उल्लेखित मिति र समयमा भरतपुर अस्पतालको [Website- eProcurement System \(bharatpurhospital.gov.np\)](http://www.bharatpurhospital.gov.np) मा फर्त अनिवार्य रूपमा पेश गर्नु पर्ने छ।
५. **Upload** भएका बोलपत्रहरू तपशिलमा उल्लेखित मिति र समयमा यस अस्पतालमा बोलपत्र दाता वानिजको प्रतिनिधिको रोहवरमा खोलिने छ। प्रतिनिधि उपस्थित नभएपनि दरभाउ पत्र खोल्न बाधा पर्नेछैन। बोलपत्र खरीद गर्ने वादाखिला गर्ने अन्तिम दिन विदा पर्न गएमा सोको भोलिपल्ट क्रमशः उक्त कार्य हुनेछ।
६. बोलपत्र दाताले कबोल गरेको प्रत्येक आइटमको दररेटलाई (मु.अ.क. बाहेक) अंक र अक्षरमा स्पष्टसँग उल्लेख गर्नुपर्नेछ। अंक र अक्षरमा उल्लेखित दररेटमा भिन्नता भएमा अक्षरलाई मान्यता दिइने छ।
७. बोलपत्र दाताले कबोल गरेको बोलपत्रमा तोकिएको परिमाण मापदण्ड अनुसार र समयमा कार्य सम्पन्न नसकेमा अन्य उपाय अवलम्बन गरी उक्त कार्य गरिनेछ। त्यसरी कार्य गर्दा बोलपत्रमा उल्लेख गरिएको मुख्य भन्दा बढी पर्न गएमा बोलपत्र दाताको धरौटी रकम वा भुक्तानी गर्न बाँकि रकमबाट असुल उपर गरिनेछ।
८. निर्माण तथा मर्मत जन्य कार्यको लागि चाहिने सम्पूर्ण सामानहरू स्पेसिफिकेशन वमोजिमको उच्च गुणस्तरको हुनपर्नेछ।
९. कुनै बोलपत्र स्वीकृत गर्ने वान गर्ने वा आशिक रूपमा स्वीकृत गर्ने सम्पूर्ण अधिकार यस अस्पतालमा सुरक्षित रहनेछ।


नि. प्र. ने. सु.



१०.निर्माण तथासर्मतको लागिप्रयोग भएकासमानहरु निरिक्षण एवं परिक्षण गर्दा सम्मौतामाउल्लेखित गुणस्तर वमोजिमकानभए सम्मौता रद्द गरिनेछ।

११.संभौता गरीकार्यनगर्ने फर्मलाई नियमानुसार कालोसूचीमादर्ताको लागि सम्बन्धितनिकायमा लेखि पठाइनेछ।

१२.शर्त रहेको,रीत नपुगेको तथाम्याद नाघी आएको वोलपत्रउपर कुनै कारवाहीहुनेछैन। एक फर्म वा सस्थाको नाममाखरिद गरिएको वोलपत्रअर्को फर्मको नामवाट पेशगर्न पाईने छैन।

१३.बोलपत्रदाताले खरिद कारवाहिमाभागलिनप्रचलितकानुनअनुसार अयोग्यनभएको, प्रस्तावितखरिद कारवाहिमाआफ्नो स्वार्थ नवाभिएको वाब्यवसाय सम्बन्धि कसुरमाआफुले सजायनपाएको भनिस्वयं घोषणा पेश गर्नुपर्नेछ। त्यस्तो स्वयम घोषण सूचनाप्रकाशितभएको मिति पछिको हुनु पर्नेछ।

१४.यसमानपरेका अन्य कुराहरु सार्वजनिक खरीद ऐन २०६३ र सार्वजनिक खरीदनियमावली २०६४ अनुसार हुनेछ।

१५. थपजानकारीको लागि यस अस्पतालको इन्जिनियरिङ्गशाखा/लेखाशाखामा सम्पर्क राख्न सकिनेछ।

तपशिल

सि. नं.	ठे.नं.	विवरण	जमानत रकम	बोलपत्र दस्तुर	बोलपत्रखरिद गर्ने अन्तिममिति	बोलपत्रदाखिलागर्ने अन्तिममिति	बोलपत्रखोले मिति	कैफियत
१	०९ ०७९।०८०	गेट निर्माण, ब्लक 'ए' पछाडि मोजाइक टाइल्स लगाउने कार्य	७०,०००।	३०००।	३०औं दिनको वैकिड समय भित्र	३१औंदिनको १२।०० वजे	३१औंदिनको १।०० वजे	

नि. प्र. मे. सु.

Government of Nepal
Ministry of Health & Population
Bharatpur Hospital
Chitwan



Job : Construction of Gate No 3, gate 2 and mosaic tile
Location : Near Hospital Annex Block, gate no 2 and behind block A.

F/Y : 079/80

BILL OF QUANTITY

S.N	Description	Quantity	Unit	Per Unit Rate (exclusive of VAT)		Amount	Remarks
				In Figure	In Words		
1	Site Clearance before and after the completion of works all complete.	1	job				
2	Site Clearance works: Bushes and grass cutting, root digging, breaking sods, clearing ground and carrying away debries from site and disposing safely all complete	246.28	sq.mt				
3	Dismantling Works: Dismantaling of brick masonry wall and reusing the useable material and dispoal of debries outside from site all complete	6.9	Cu.mt				
4	Earthwork excavation in Gravel mixed soil in foundation including stacking the soil 1 m from the edge of the foundation and 10m hauling distance and 1.5m lift all complete as per instruction by site engineer.	13.78	Cu.mt				
5	Stone Soling Work: Supplying and laying stone with sand compaction	2.76	Cu.mt				
6	P.C.C. in 1:3:6 (M10)work for levelling in ground with approved quality of cement and sand and crushed stone aggregate including mixing,laying,curingetc all as per instruction and specification all complete.	2.99	Cu.mt				

Prashant
नि. प्र. मे. सु.



7	Formworks for Columns, shear walls: Supplying, laying and fitting 19mm plywood formworks for column including metal props, clamps and other supportive materials, erection, nailing and removing after specified time with transportation upto 30m. (formwork on 2m dia column)	101.43	Sq.mt				
8	Good quality local chimney made Brickwork in 1:6 C/S mortar upto Ground Floor in perfect line level finished including material and transportation up to 30m, wetting the bricks, racking the joints and curing the work for at least 7 days all complete.	10.35	Cu.mt				
9	Good quality machine made Brickwork in 1:6 C/S mortar Upto Ground Floor in perfect line level finished including material and transportation up to 30m, wetting the bricks, racking the joints and curing the work for at least 7 days all complete.	19.24	Cu.mt				
10	Steel reinforcement works: Supplying, Cutting, bending & placing of reinforcement bars in position as shown in the drawings and binding by approved binding wires for RCC works with 30 m lead, as per A/E instructions all complete	2509.33	k.g				
11	(PCC) for RCC works: Preparing Machine Mix concrete grade M20 for foundation, foundation beam, bands etc. with approved quality of cement, sand and crushed stone aggregate (12-40mm) including mixing, compaction, laying, curing etc. in perfect line level and plumb for any size, location and shape all complete work as per drawing, specification and instruction of A/E.	63.57	cu.mt				

Prashant
नि. प्र. मे. सु.




12	Supplying of 16 gauge metals of different shapes (with 50*50*5mm frame size) and fabricating and installing on site as per instruction with a coat of red oxide.	45.65	Sq.mt				
13	Colouring with silicon paint of approved color on brick wall face to give uniform colouring after rendering the surface as per specification and instruction of site engineer all complete.	112.1	Sq.mt				
14	2 coats of enamel paint of approved colour to give uniform coloring after rendering the surface on wall, column etc over properly cleaned surface all complete.	97.3	Sq.mt				
15	Supplying of natural gravel, laying, spreading and compacting after sprinkling of water to the required thickness all complete.	19.5	Cu.mt				
16	Supplying of hexagon interlocking paver (multi colour) with compressive strength M25 or above, thickness =60mm (size 226mm*200mm*60mm) placed over the suitable base and filling the joints with stone dust all complete.	246.28	sq.mt				
17	Supplying and fitting metal works with different deections of angles, plates, pipes rods, end caps etc. with proper weldings with primer, complete as per instructions and specifications	291.08	k.g				

Prashant
नि. प्र. मे. सु.



18	Supplying, wiring, testing and commissioning and putting into operation of lights points using 2 nos 2.5 sq mm + 1sq mm multi stranded copper conductor, 1100 volts grade, PVC insulated wires drawn through pre-installed 20 mm dia rigid HDP pipe as a cable sleeve concealed in wall, ceiling and floor and/or on surface including all fixing and connecting materials. The rate for point wiring shall include the circuit wiring from designated Distribution Board (DB) up to the first light switch on wards to light then the looping between switches /lights etc. (No cable jointing is allowed except switch and fixture). The cost shall be including 5 nos. 50 watt IP66 rated LED lights, 2 nos. 16A power sockets, 10 nos 18 watt LED surface mounted rigid HDP pipe, control switches/electronic fan dimmers integrated in multi modular plate flushed in required size of GI box, GI fish wire, cutting and filling chases for recessed pipes as deemed as per drawing and lay out plan all complete.modular switches and Fan dimmer shall be - Dyna / CPL or equivalent. Cables and Wires: Litmus / Nepal / Janta or equivalent.						
	Total Amount		1	job			
	13 % Vat						
	Total Amount						


नि. प्र. मे. सु.



	Name of Company :	
	Address :	
	Date :	
	Seal and Signature :	

Fresh
नि. प्र. मे. सु.